



# Response of Some Microorganisms, Earthworms and Snails to Pesticides (Carbofuran and Paraquat) under Tropical Conditions

Ataikiru T. L. <sup>a\*</sup> and Okorhi F. B. <sup>a</sup>

<sup>a</sup> *Department of Environmental Management and Toxicology, Federal University of Petroleum Resources, Effurun, Delta State, Nigeria.*

## **Authors' contributions**

*This work was carried out in collaboration between both authors. Author ATL designed the study, wrote protocol, managed the analyses and performed the statistical analysis. Author OFB wrote the first draft of the manuscript and managed the literature searches. Both authors read and approved the final manuscript.*

## **Article Information**

### **Open Peer Review History:**

This journal follows the Advanced Open Peer Review policy. Identity of the Reviewers, Editor(s) and additional Reviewers, peer review comments, different versions of the manuscript, comments of the editors, etc are available here: <https://prh.globalpresshub.com/review-history/1533>

**Original Research Article**

**Received: 10/01/2024**  
**Accepted: 14/03/2024**  
**Published: 19/03/2024**

## **ABSTRACT**

**Aim:** to determine the response of microorganisms, earthworms and snails to pesticides under tropical conditions.

**Study Design:** soil experiment with a controlled lighting system of 12 hour of light and 12 hour of darkness was adopted.

**Place and Duration of Study:** Department of Environmental Management and Toxicology, Federal University of Petroleum Resources, Effurun, Nigeria/three months.

**Methodology:** Acute effect of pesticides on earthworms and snails was assessed using a 14 day soil bioassay test as recommended by Organization for Economic Cooperation and Development (OECD) and International Organization for Standardization (ISO). Effect of pesticides application on microorganisms in soil was evaluated via standard microbial counts.

**Results:** Toxicity of Carbofuran to the earthworms and snails was higher relative to Paraquat with a median lethal concentration (LC<sub>50</sub>) of 10.7 mg/kg; 159571 mg/kg (earthworms) and 23.22 mg/kg;

\*Corresponding author: Email: [ataikiru.tega@fupre.edu.ng](mailto:ataikiru.tega@fupre.edu.ng);

759000mg/kg (snails), respectively. Microbial counts increased in pesticides treated soil after the initial decline in numbers. Total heterotrophic bacterial counts in Carbofuran and Paraquat treated soils increased from  $1.59 \times 10^6$  CFU/g to  $2.41 \times 10^6$  CFU/g and  $1.46 \times 10^6$  CFU/g to  $2.08 \times 10^6$  CFU/g, respectively for day 14 to 21. A reverse trend was observed in control soil. Fungal counts increased in Carbofuran ( $1.18 \times 10^5$  CFU/g to  $1.42 \times 10^5$  CFU/g); Paraquat ( $1.53 \times 10^5$  CFU/g to  $1.79 \times 10^5$  CFU/g) from day 14 to day 21. Actinomycetes counts were in magnitude of  $10^4$  CFU/g soil for both Carbofuran and Paraquat treated soils, while population of phosphate solubilizers and nitrifiers were in  $10^5$  CFU/g soil.

**Conclusion:** Toxicity test estimates the possibility that antagonistic environmental impacts/influence might take place or are taking place due to exposure to sole or additional pesticides. Pesticides had no adverse effects on the microorganisms at recommended field rates. Thus, their use must strictly be based on these recommended rates.

*Keywords: lethal toxicity, pesticides, microorganisms, snails, earthworms, tropics.*

## 1. INTRODUCTION

Pests refer to biotic constituents of the environment like fungi, insects, birds, other mammals, microorganisms and weeds that cause injuries to plants and animals that man invest in and rely on for food material to maintain life [1,2,3]. Their overall effect on crops and livestock is the decrease of yields to an uneconomical point for the agriculturalist to remain in the business [4,5,6]. High demand is placed on the supply of food to support the ever increasing world population. In other to increase food production to meet the alarming increase population has led to the introduction of pesticides [7,8].

Pesticides are formulations used to kill or manage pests at tolerable levels. They can be natural or synthetic. The use of pesticides has its positive and negative effects. The indiscriminate use of these substances has led to contamination of soil, ground water, lakes and man [9]. Pesticides are classified based on their mode of application and action, target organisms, desired goal, chemical composition among others [10,11].

Carbofuran (2,3-dihydro-2,2-dimethylbenzofuran-7-yl-N-methyl carbamate) is a broad spectrum, systemic, non-ionic, acaricide/insecticide and nematicide included in the general group of the carbamate derivative pesticides. It is widely used for the control of soil dwelling and foliar feeding insects including wireworms, white grubs, weevils, stem borers, aphids and several other insects [12].

Paraquat (N, N'-dimethyl-4,4'-bipyridinium dichloride) is termed a chemical flame gun, in so much as it kills the above-ground parts of plants

whilst not damaging the roots. Paraquat inhibits photosynthesis and applied post emergence to leaf tissues [13]. Paraquat is a non - selective herbicide used to control most yearly weeds and several broad leaf weeds in field corn, potatoes, rice, cotton, soybeans, tobacco, peanuts and sunflowers [14].

Soils are termed polluted when the concentration of the contaminant exceeds the level defined by the application regulations. Data from chemical analysis of soil, water and food samples are not enough indication of the degree and source of pollution [15]. Hence, there's need for bioassays to provide useful and important information on the risks posed by these pesticides to the biotic population [16].

Microorganisms are biological indicators in the soil environment. They are very sensitive to manmade or foreign disturbances and climate change. Microorganisms act as excellent measures of soil integrity. The conventional method of evaluating the diverse nature of microorganisms relies on their potential to grow and form visible colonies on solid media [17]. The method provides useful information on the active and heterotrophic microbial diversity within the population.

Earthworms make up over 80% of the biomass of soil invertebrates and are important in structuring and nutrient cycling in the soil. Earthworms are seen as suitable bio-indicators of anthropogenic contamination. Earthworms are used in ecological risk assessment because they ingest large quantities of decomposed organic matter in soil converting it to rich topsoil. Also, their skin is a significant route of toxicant uptake. Mortality has been the most frequently used indicator in assessing chemical toxicity on earthworms [16, 18,19,20,21,22,23,24,25].

The non-existence of hard cuticle around their body makes them appropriate bioindicators of soil pollution, and could be employed to offer thresholds for pesticide usage [26]. It has been proven from studies that increased amounts of pesticide deposits in farm soils impose a greater threat to soil fauna and these harmful impacts on soil fauna may disrupt the processes they drive, including those related to organic matter decomposition, nutrient cycling, and preservation of soil structure [27]. Acute toxicity of earthworm is an efficient tool in ecological risk assessment of polluted soils and endpoint is mortality [28]. According to Bhandari et al. [29], earthworms are among the first receptors affected by soil pollution and are highly responsive to metals and pesticides than any other group of soil invertebrates. Data on toxicity of earthworm are key in assessing the "safe levels" for stressors in soil.

The Organization for Economic Cooperation and Development (OECD) method has two approaches to the analysis of toxicants; the filter paper test and soil test method. The former is useful for screening while the latter is a better depiction of the natural environment as the earthworms absorb these pesticides through their guts [30]. Hence, the toxic impact of pesticides can be adequately determined using the soil test. According to Bart et al. [31], earthworms are considered as important bioindicators of chemical toxicity in the soil ecosystem. Such study is vital because earthworms are common prey of many vertebrates like birds and small animals, thus are fundamental in the biomagnification process of many soil pollutants.

Among the lower tier earthworm tests are the acute toxicity and chronic toxicity test. The acute toxicity test detects qualitative effects and lethality of the toxicants while the chronic detects the sub-lethal impacts like retarded development, reduced fertility and teratogenic effects. These testings are advantageous as they are fast, cost-effective and sometimes are higher in sensitivity relative to other toxicity test [23,32]. These tests are standardized, recognized and promoted at international levels by Organization for Economic Cooperation and Development (OECD) and International Organization for Standardization (ISO). Alves et al. [18], reported that only a few researches have been performed on the effects of pesticides application on earthworms under tropical scenerios. Moreover, a risk assessment based on temperate data could be less

appropriate for tropical conditions, therefore, this study.

Snails are important indicators of terrestrial ecological risk assessment; they are soil surface dwellers because major stages of their life-cycle rely on the soil (laying, hatching, preliminary/early growth stages and hibernation). They get nutrition from decomposing organic matter and plants [33,34]. These terrestrial animals were chosen because they are eaten by man and other higher animals as good source of protein [35]. Exposure of these fauna to toxicants could lead to dangerous impacts on them and several species higher the food-chain/web [29]. Furthermore, a risk assessment based on types of pesticide could be appropriate for tropical conditions. Hence, the essence for this study.

## **2. MATERIALS AND METHODS**

### **2.1 Study Area**

The study area was located in the Federal University of Petroleum Resources, Effurun, Delta State, Nigeria (7° 23' N; 3° 51'E and 26.7m above mean sea level). The Niger Delta experiences tropical climate with distinct wet and dry seasons having a bimodal rainfall pattern with rainfall peaks mostly in June to September and average temperature of 25.2°C (78.8°F) - 28°C (82.4°F). The soils were mostly sandy loam at the top, to brown loamy sand sub soil and well drained. Three different representative locations having similar ecological conditions were selected. The locations had no history of pesticide applications.

### **2.2 Test Pesticides**

The pesticides used for this study were Carbofuran and ParaQ. Pesticides (Carbofuran and Paraquat) were purchased from local retailers in Warri, Delta State. These pesticides were chosen because of their popular use in potato, maize, groundnuts farming and flower lawns in the Niger Delta region. The Carbofuran formulation contained (5%) and ParaQ formulation contained 200g/l Paraquat. These formulations were used as stock and different concentrations were prepared for the range finding and definitive tests.

### **2.3 Test Species**

The test organisms used in this research were recommended by Organization for Economic Development (OECD) and International Organization for standardization (ISO). The

organisms were obtained from their natural habitat with no history of pesticides use at Federal University of Petroleum Resources (FUPRE), Effurun, Delta State. The test organisms were earthworms (*Lumbricus terrestris*) and snails (*Helix aspersa*). Healthy test species were collected by hand sorting from cultured farms in FUPRE.

#### **2.4 Earthworm and Snail Ecotoxicity (Acute Toxicity Test)**

The 14 day acute toxicity test was carried out in accordance with the protocol adopted from [36] and [16] for earthworms (*Lumbricus terrestris*) and the International Organization for Standardization [35] protocol for snails. Garden snails, *Helix aspersa* were collected from farms with no pesticide history. The selected snails and earthworms were well cleaned; kept in large plastic containers and acclimatized for 7 days before the experiments. The natural topsoil was gotten from the field from which the test animals were collected. The test started with a range finding test to decide the definitive test concentrations. Homogenized and air dried soil were sieved through 2 mm mesh. Adult earthworms were exposed to soil mixed with different concentration of pesticides. The definitive test concentrations for Paraquat were 625, 1250, 2500, 5000, 10000mg/kg and 0.3125, 0.625, 1.25, 2.5, 5.0mg/kg for Carbofuran, respectively. Immediately before the test, the earthworms were washed and weighed individually. Only those with 250 – 300mg weight were selected for the assay. The different test media were polluted with 80ml (test solution) of the various concentrations. The worms were washed with deionized water, placed on absorbent paper for a short period to allow excess water to drain. The test organisms were placed on filter paper for one hour to void the contents of their gut. Ten earthworms were placed on 1000g of natural soil (with different concentrations of pesticides) in a glass bottle/container of 1.2L capacity and allowed to borrow. The earthworms were fed with 5 grams urine-free dried and ground cattle manure (cow dung's) once a week during the experiment. Five grams of fresh pawpaw leaves were placed in each test container as food for the snails to prevent them from starving during study. The snails were kept on moist filter paper to void contents of their stomach before placing them in the test containers. Each container contained ten snails. These set up in three replicates per treatment were prepared for five exposure

concentrations and control were also prepared using distilled water. The trial was done at  $28\pm 1^{\circ}\text{C}$ .

#### **2.5 Assessment of Mortality**

Mortality of earthworms and snails were evaluated at day 7 and 14 to determine the lethal concentration of each pesticide. To check the mortality, the test containers were emptied onto a clean tray and earthworms were sorted from soil. Earthworms were considered dead when they failed to show a reaction to gentle mechanical stimulations with a blunt probe. Live organisms were counted at completion of trial. Direct contact was avoided to prevent induced stress on the test animals. Live organisms were counted and physical alterations were noted. Some snails hibernated secreting a mucus calcareous substance. Test organisms were considered dead under conditions of no movement when the foot region was prodded by a blunt probe or no movement when placed on filter paper and water sprinkled on them for five minutes. Probit analysis was employed to ascertain median lethal concentration.

#### **2.6 Microbial Assay**

This experiment was performed in pots set-up as randomized block design arranged out in four different blocks. Three kilograms (3kg) of unpolluted soil were weighed in 5L pots. The pots were sprinkled with the pesticides (Carbofuran and Paraquat) individually for a duration of eight weeks at company specified amounts [37]. The control pots received no pesticides but sterile deionised water. Top soil samples (0-5 cm) were obtained from each pot aseptically [38]. Ten soil samples were obtained at random from each pot and thoroughly mixed together to form a composite sample. The influence of various pesticides on soil with respect to microbial growth were evaluated and compared with control soil (without treatment) in replicates every week after the treatment period of eight weeks. The population count of microorganisms was carried out by traditional viable cell counts. One (1) gram of each soil sample was suspended in 9 ml of sterile distilled water. Serial dilution was done aseptically under laminar flow. Aliquots (0.1ml) of the dilutions were plated out using appropriate media for the enumeration of microorganisms. Rose-Bengal chloramphenicol agar was used for the enumeration of fungi [39]. Plate count agar (PCA) was used for the enumeration of

heterotrophic bacteria [40]. Actinomycetes were enumerated using starch-casein agar [41] and Pikovskaya's medium for phosphate solubilizing microbes [39]. Ashby agar was used to enumerate nitrogen fixers [38] and individual colonies were recorded as colony forming units (CFU) [42].

## 2.7 Statistical Analysis

The susceptibility of the test species (earthworms and snails) to the toxicants were determined using the probit method of analysis for the lethal concentration  $LC_{50}$  at day 14. The mean statistical difference between the controls and treatment groups at significance levels of  $p < .05$  were evaluated for microbial counts using the analysis of variance (ANOVA).

## 3. RESULTS AND DISCUSSION

### 3.1 Acute Toxicity Assay Using Earthworms

The Probit results obtained from exposing the earthworms to Carbofuran and Paraquat contaminated soil are presented in Fig. 1 and Fig. 2. The median lethal concentration  $LC_{50}$  of Carbofuran was 10.7mg/kg while that of Paraquat was 159571mg/kg suggesting that the former was more toxic than the latter.

This study tested the effect of Carbofuran and Paraquat on survival of *Lumbricus terrestris* using standardized ecotoxicological tests (after

OECD guidelines with few adaptations for tropical conditions). Commercial formulations of Carbofuran and Paraquat were tested individually in tropical soil. The pesticides tested were lethal to *L. terrestris*, but noxious level obtained hinged on concentrations used. The probit outcome of hither research revealed  $LC_{50}$  of Carbofuran as 10.7mg/kg while that of Paraquat was 159571mg/kg hence, Carbofuran was more lethal than Paraquat. From our findings, Carbofuran was very lethal and Paraquat practically not toxic conferring to soil toxicity rating [43]. Similar reports have been published for pesticides in diverse investigations. Yuguda et al. [20], in their studies reported variations in toxicity of a number of pesticides (insecticides, fungicides and herbicides) to *L. terrestris* and established that insecticides were more poisonous than herbicides. This was in corroboration with our findings. Carbofuran induced high toxic effect by revealing high magnitude of mortality while paraquat demonstrated rather lesser fatal effect. In addition, worms displayed other physical behaviours such as coiling and swelling due to toxicity of pesticides (Carbofuran and Paraquat). Different researchers have reported that animals' progressive change in signs and symptoms due to toxicity levels range from visibly undetectable marks to coiling, extrusion of coelomic fluid, segmental constriction and swelling. In several animals the swollen portion burst causing bloody lesions, limp and eventually death [19,21].





Fig. 1. Median lethal concentration ( $LC_{50}$ ) of Carbofuran for earthworms = 10.7mg/kg



**Fig. 2. Median lethal concentration (LC<sub>50</sub>) of Paraquat for earthworms = 159571mg/kg**

When interpreting ecotoxicological test in predicting environmental risk, death is a major factor measured for drop in numbers of topsoil organisms. So many researchers have reported reduction in worms' abundance, in which some have attributed the reduction to limitations in putrefaction of organic matter. Furthermore, population reductions are rarely interconnected with lethal effects.

Lima et al. [43], recounted some pesticides may possibly present a low lethal risk to earthworms in the wild (natural conditions), and that lower abundance maybe as a consequence of organisms' ability to avoid areas that are seriously contaminated with these toxicants. Declines in their numbers may well be traceable to impacts on reproduction; including the malformation of gametes and embryos, inability to hatch and teratogenic effects [16]. Patel & Prajapati [22] reported a hyper toxicity (LC<sub>50</sub> = 0.9ppm) of cypermethrin (that is used in farms to control mites) to earthworms, *Eisenia fetida*. Furthermore, [24] in their findings stated that acetamiprid exhibited an LC<sub>50</sub> of 6.69mg/kg on *Lumbricus terrestris*. In our study, the tested pesticides caused mortality of test animals (earthworms).

### 3.2 Acute Toxicity Assay Using Snails

The Probit results obtained from exposing the snails to Carbofuran and Paraquat contaminated soil are presented in Fig. 3 and Fig. 4. The median lethal concentration LC<sub>50</sub> of Carbofuran was 23.22 mg/kg while that of Paraquat was 759000 mg/kg for the snail.

This study showed that increases in pesticide concentration resulted in mortality of test snails presenting a correlation between concentration and mortality or death. Carbofuran had an LC<sub>50</sub> value of 23.22 mg/kg whereas Paraquat had 759000 mg/kg. From the results, Carbofuran was highly poisonous to snails while Paraquat was not underpinning soil toxicity rating prescribed by the Organization for Economic Co-operation and Development [42]. The LC<sub>50</sub> showed that Carbofuran was highly harmful to snails than Paraquat. This report is analogous with previous reports on species where the toxicant concentrations interrelated with lethality of test animals [44]. Ogeleka et al. [16], reported LC<sub>50</sub> value of Grassate as 1.731 ± 0.05mg/kg which connotes lethality. Ogeleka et al. [16], carried out an investigation on the lethal and sub-lethal impact of a non-selective herbicide, Grassate on

snails (*Achachatina margarita*) and reported a median lethal concentration  $LC_{50}$  toxicity of  $1.73 \pm 0.05$  mg/kg. This result was a pointer that Grassate was “extremely toxic” and such ought not to be administered indiscriminately. Also, they noticed a reduction in biomass (26 - 65% reduction in weight) with increased concentrations for the species. Also, [23] recounted that Renovan (chlorpyrifos) had an  $LC_{50}$  value of 9.6mg/L and a molluscidal effect on *Biomphalaria alexandrina* snails. Our study established that Carbofuran, a carbamate had a noteworthy impact on snails during exposure and may perhaps cause a drastic drop in population of these viable animals.

### 3.3 Microbial Counts

Figure 5 shows the bacterial counts during the experiment. The total heterotrophic bacterial counts increased in all the pesticides treated soil after the initial decline in numbers.

Total heterotrophic bacterial (THB) counts in Carbofuran and Paraquat treated soils increased from  $1.59 \times 10^6$  CFU/g to  $2.41 \times 10^6$  CFU/g and

$1.46 \times 10^6$  CFU/g to  $2.08 \times 10^6$  CFU/g, respectively for day 14 to 21. A reverse trend was observed in counts from control soil. Diez et al. [45], reported an initial drop in numbers of heterotrophic bacteria and fungi, but counts amplified as the days progressed after the application of pesticides in soil. This was partly observed during our study.

Fungal counts obtained from the study is shown in Fig. 6. There was a general decrease in fungal counts in the different treatments initially except the control soil.

Fungal counts amplified in Carbofuran ( $1.18 \times 10^5$  CFU/g to  $1.42 \times 10^5$  CFU/g); Paraquat ( $1.53 \times 10^5$  CFU/g to  $1.79 \times 10^5$  CFU/g) from day 14 to day 21 and were in the magnitude of  $10^4$  to  $10^5$  CFU/g for both pesticides. There were increases in fungal population throughout the study from  $1.50 \times 10^5$  CFU/g to  $1.91 \times 10^5$  CFU/g for the control soil.

Actinomycetes counts in response to the different treatments are represented on Fig. 7.






Fig. 3. Median lethal concentration ( $LC_{50}$ ) for snails in Carbofuran = 23.22 mg/kg



**Fig. 4. Lethal concentration (LC<sub>50</sub>) for snails in Paraquat = 759000mg/kg**




**Fig. 5. Total heterotrophic bacterial counts**

The actinomycetes counts increased for both treatments from day 14 to day 21, followed by a decline (day 28). Counts increased from  $1.41 \times 10^4$  CFU/g to  $2.11 \times 10^4$  CFU/g for Carbofuran and  $1.73 \times 10^4$  CFU/g to  $2.43 \times 10^4$  CFU/g for Paraquat. The reverse was the trend for the


control soil from  $1.97 \times 10^4$  CFU/g to  $1.27 \times 10^4$  CFU/g.

Fig. 8 shows the phosphate solubilizers counts during the experiment. Phosphate solubilizers' counts dropped throughout study.






**Fig. 6. Fungal counts in the different treatments**



**Fig. 7. Actinomycetes counts in the different treatments**



**Fig. 8. Phosphate solubilizers counts in the different treatments**

In Carbofuran treated soil, the phosphate solubilizers increased from  $1.55 \times 10^5$  CFU/g to  $1.95 \times 10^5$  CFU/g and  $1.93 \times 10^5$  CFU/g to  $2.13 \times 10^5$  CFU/g for Paraquat at days 14 and 21, respectively.

The nitrifying bacterial counts obtained during this study is shown in Fig. 9. Furthermore, there was an initial drop in the nitrifiers counts (day 7) and thereafter increases at day 14 and day 21.


The counts increased from  $1.67 \times 10^5$  CFU/g to  $1.89 \times 10^5$  CFU/g for Carbofuran treated soil and  $1.98 \times 10^5$  CFU/g to  $2.20 \times 10^5$  CFU/g for Paraquat treated soil. On the other hand, there was a gradual decline in counts from  $1.80 \times 10^5$  CFU/g to  $1.42 \times 10^5$  CFU/g in the control soil.

Microorganisms are used to consider responses to anthropogenic pollution because microbial cells are in direct contact with their environment and are sensitive to these disturbances [46,47,48,49,50]. However, those that are competent and adjust to these ecological changes become the most dominant microbial species. This ability to adjust to anthropogenic disturbances allows microbial analyses in discerning soil health status, shifts in microbial populations and activities; hence, can perform excellently as indices of soil health fluctuations. Sometimes, dynamics in microbial community structure or function provides prompt signal of soil enhancement or caution of soil degeneration

prior to demonstrable alterations in chemical and physical properties [51].

The present day study has revealed that the effect of different chemicals/toxicants on microbial populations reduced with time. Increases in counts after initial suppression were pointers to microbial recovery from shock presented by the stressors; their adaptations to these toxicants and their abilities to degrade them. Furthermore, these increases could be traced to the proliferation of microbes on the larger volume of utilizable nutrients released by the dead segment of the populations [52,53,54]. There are reports that several microorganisms possess the ability to breakdown pesticides while others lack such abilities and are highly affected by the type of pesticide and dose applied [46,55].

Hence, pesticides either stimulate or suppress population depending on agrochemicals (type/formulation and concentration), method of use, microbial groups and ecological conditions [55,56]. It has been established that availability of high organic matter accelerates herbicides degeneration in soils, possibly because of dynamic microbial action/exertions. The use of herbicides can reduce total microbial populations in soil, where some studies have traced it to reduced input of organic residues [38]. The more organic matter present in a soil, the longer an insecticide persists in it. According to several researchers [57,58,59] pesticides leads to qualitative and quantitative adjustment in soil microbial communities/groups.



**Fig. 9. Nitrifiers counts in the different treatments**

Culture-dependent protocol revealed that there was an increase in total heterotrophic bacteria (THB) population in both pesticide treated soils, after an initial decrease in counts was observed during this study. Bacterial counts were in the magnitude of  $10^6$  CFU/g soil for Carbofuran and Paraquat treatments. Jiang et al [60] reported that the long term application of acetochlor had no significant impact on the overall soil microbial community composition after years of application.

A significant difference ( $P= 0.05$ ) was recorded in fungal counts with reference to both pesticides and duration (time). Fungal counts increased from  $10^4$  CFU/g soil to  $10^5$  CFU/g soil for Carbofuran and Paraquat-treated soils. Actinomycetes counts were in magnitude of  $10^4$  CFU/g soil for both Carbofuran and Paraquat treated soils, while population of phosphate solubilizers and nitrifiers were in  $10^5$  CFU/g soil.

#### 4. CONCLUSION

Research has shown that pesticides have caused serious impact on soil environment. Such soils have negative effects on humans and the natural ecosystem. There's need for the

protection of the health of the natural terrestrial ecosystem and in turn protect human health as well as other vertebrates and invertebrates. Growth of earthworms and snails exposed to agro-pesticides are useful bio-indicators of soil pollution. Acute toxicity test indicated test organisms (earthworms and snails) were more endangered by Carbofuran ( $LC_{50}$  10.7 mg/kg; 23.22 mg/kg) relative to Paraquat ( $LC_{50}$  159571 mg/kg; 759000 mg/kg), respectively. Toxicity test estimates the possibility that antagonistic environmental impacts/influence might take place or are taking place due to susceptibility to sole or additional pesticides.

In practice, pesticides are applied multiple times under various environmental conditions, and commercial formulations contain a range of additional compounds that are not disclosed. The soil used in this study was collected from a pesticide free environment. Therefore, it is possible that either pesticide-tolerant organisms were present or these organisms developed the abilities. Despite being largely consistent with previous studies, our results must be inferred with restraint and additional work is crucial to effusively understand the impending influences of pesticides on soil microbial populations.

Pesticides caused transient impact on microbial populations at recommended field application rate and were particularly sensitive to small changes in the environment. The gradual increase in microbial counts may be attributed to their ability to temporarily mineralize and use pesticides as energy source. No research is encompassing, hence there's need to assess information on the chemical nature, mode of action and approaches to degradation of these toxicants in the terrestrial ecosystem to reduce the negative effects to fauna and organisms at higher trophic levels.

### COMPETING INTERESTS

Authors have declared that no competing interests exist.

### AUTHORS' CONTRIBUTIONS

### REFERENCES

1. Wood TJ, Goulson D. The environmental risks of neonicotinoid pesticides: a review of the evidence post 2013. *Environ. Sci. Pollut. Res.* 2017;24:17285–17325.
2. Dar MA, Baba ZA, Kaushik G. A review on phorate persistence, toxicity and remediation by bacterial communities. *Pedosphere.* 2022;32(1):171-183.
3. Joko T, Dewanti NAY, Dangiran HL. Pesticide Poisoning and the use of personal protective equipment (PPE) in Indonesian farmers. *Journal of Environmental and Public Health.* 2020; 1-7.
4. Phaceli A, Kone M, Dembele A, Haba J, Yao E. Effect of Herbicides Used in Horticulture (2,4-D, Glyphosate and Nicosulfuron) on Snails *Achatina fulica* (Bowdich, 1720). *Journal of Agricultural Chemistry and Environment.* 2021;10: 402-414.
5. Bonvoisin T, Utyasheva L, Knipe D, Gunnel D, Eddleston M. Suicide by Pesticide Poisoning in India: A Review of Pesticide Regulations and their Impact on Suicide Trends. *BMC Public Health.* 2020;20:251.
6. Mohring N, Ingold K, Kudsk P, Martin-Laurent F, Niggli U, Siegrist M, Studer B, Walter A, Finger R. Pathways for advancing pesticide policies. *Nature Food.* 2020;1(9):535–540.
7. Sarwar M. The killer chemicals for control of agriculture insect pests: The botanical insecticides. *International Journal of Chemical and Biomolecular Science.* 2015;1:123–128.
8. Ojo MO, Zahid A. Deep learning in controlled environment agriculture: a review of recent advancements, challenges and prospects. *Sensors.* 2022; 22:7965.
9. Dar MA, Kaushik G, Francisco J, Chiu V. Pollution status and biodegradation of organophosphate pesticides in the environment, Editor(s): Pardeep Singh, Ajay Kumar, Anwasha Borthakur, Abatement of Environmental Pollutants, Elsevier. 2020;25-66.
10. Benicha M, Mrabet R, Azmani A. Dissipation processes of <sup>14</sup>C-carbofuran in soil from Northwest Morocco as influenced by soil water content, temperature and microbial activity. *Journal of Environmental Chemistry and Ecotoxicology.* 2013;5(5):119-128.
11. Palaniyappan J, Venugopal D, Duraisamy E, Beerappa R. Pesticides and human health implications, In (eds): Mohammad Hadi Dehghani, Rama Rao Karri, Ioannis Anastopoulos, *Pesticides Remediation Technologies from Water and Wastewater*, Elsevier. 2022;3-21.
12. Dey D. Impact of indiscriminate use of insecticide on environmental pollution. *Internat. J. Plant Protec.* 2016;9(1):264-267.
13. Moretti ML, Shrestha A, Hembree KJ, Hanson BD. Post emergence control of glyphosate/paraquat-resistant hairy fleabane (*Conyza bonariensis*) in tree nut orchards in the Central Valley of California. *Weed Technology.* 2015;29 (3):501–508.
14. Hawkes TR. Mechanisms of resistance to paraquat in plants. *Pest Management Science.* 2014;70(9):1316–1323
15. Tudararo-Aherobo LE, Okorhi- Damisa FB. Comparative study of metagenomic profile of bacteria strains present in an abandoned artisanal refinery site in Obi-Ayagha Community, Delta State, Nigeria. *Journal of Applied life Sciences International.* 2023a;26(3):30-40.
16. Ogeleka DF, Onwuemene CJ, Okieimen FE. Toxicity potential of Grassate a non-selective herbicides on snails (*Achatina marginata*) and earthworms (*Aporrectodea longa*). *Chemistry and Ecology.* 2017; 33(5):447- 463.

17. Keer JT, Birch L, Molecular methods for the assessment of bacterial viability. *Journal of Microbiological Methods*. 2013;53:175-183.
18. Alves PRL, Cardoso EJBN, Martines AM, Sousa JP. Earthworm ecotoxicological assessment of pesticides used to treat seeds under tropical conditions. *Chemosphere*. 2013;90:2674-2682.
19. Ahmed ST. The Impact of four pesticides on the earthworm (*Lumbricus terrestris*). *International Journal of Current Research and Review*. 2013;5(21):01-05.
20. Yuguda AU, Abubakar Z A, Jibo AU, Abdulhameed A, Nayaya AJ. Assesment of toxicity of some agricultural pesticides on earthworm (*Lumbricus terrestris*). *American-Eurasian Journal of Sustainable Agriculture*. 2015;9(4):49-59.
21. Miglani R, Bisht SS. World of earthworms with pesticides and insecticides. *Interdisciplinary Toxicology*. 2019; 12(2): 71–82
22. Patel P, Prajapati R. Possible toxicological effect of pesticides, cypermethrin on earthworm (*Eisenia fetida*). *International Journal of Research in Engineering, Science and Management*. 2020;3(12):138-143.
23. Ibrahim AM, Hussein AAA. Toxicological impact of organophosphorus Chlorpyrifos 48%EC pesticide on hemocytes, biochemical disruption, and molecular changes in *Biomphalaria alexandrina* snails. *Pesticide Biochemistry and Physiology*. 2022;186:105154.
24. Berrouk H, Necib A, Hamaizia Y, Chabi, C-B, Hmaidia K. Acute Toxicity of an insecticide (Acetamiprid) on *Lumbricus Terrestris*. *Animal Research International*. 2023;20(1):4726–4733.
25. Gunstone T, Cornelisse T, Klein K, Dubey A, Donley N. Pesticides and Soil Invertebrates: A Hazard Assessment. *Front. Environ. Sci*. 2021;9:643847.
26. Bart S, Laurent C, Pery ARR, Mouglin C, Pelosi C. Differences in sensitivity between earthworms and enchytraeids exposed to two commercial fungicides. *Ecotoxicol. Environ. Saf*. 2017;140:177–184.
27. Alves PRL, Elke CN, Cardoso JBN, Martinesa AM, Sousa JP, Pasinic A. Seed dressing pesticides on springtails in two ecotoxicological laboratory tests. *Ecotoxicology and Environmental Safety*. 2014;105:65-71.
28. Wang K, Pang S, Mu X, Qi S, Li D, Cui F, Wang C. Biological response of earthworm, *Eisenia fetida*, to five neonicotinoid insecticides. *Chemosphere*. 2015;132:120–126.
29. Bhandari G, Atreya K, Scheepers PT, Geissen V. Concentration and distribution of pesticide residues in soil: non-dietary human health risk assessment. *Chemosphere*. 2020;253:126594.
30. Rico A, Sabater C, Castillo MA. Lethal and sub-lethal effects of five pesticides used in rice farming on the earthworm *Eisenia fetida*. *Ecotoxicol and Environ Saf*. 2016;127:222–229.
31. Bart S, Amosse J, Lowe CN, Mouglin C, Pery ARR, Pelosi C. *Aporrectodea caliginosa*, a relevant earthworm species for a posteriori pesticide risk assessment: current knowledge and recommendations for culture and experimental design. *Environ. Sci. Pollut. Res. Int*. 2018; 25:33867–33881.
32. Jeyanthi V, Paul JAJ, Selvi BK, Karmegam N. Comparative Study of Biochemical Responses in Three Species of Earthworms Exposed to Pesticide and Metal Contaminated Soil. *Environ Process*. 2016;3:167–178.
33. Gouissi FM, Adimi AE. Bioavailability of Agricultural Pesticides on the Land Snails in the Commune of Kérou in the North of Benin. *Open Journal of Soil Science*. 2019;9(7):
34. Wang G, Shi, H, Du, Z, Chen H, Peng J, Gao S. Bioaccumulation mechanism of organophosphate esters in adult zebrafish (*Danio rerio*). *Environmental Pollution*. 2017;229:177 –187.
35. International Organization for Standardization (ISO). Protocol for testing soil quality #15952 – effects of pollutants on juvenile land snails (*Helicidae*) – determination of the effects on growth by soil contamination. Paris; 2006.
36. Organization for economic cooperation and development (OECD). Earthworm, acute toxicity test. OECD guideline for testing chemicals 207. Paris: OECD: 1984;1-9.
37. Wibawa W, Mohamad RB, Puteh AB, Omar D, Juraimi AS, Abdullah SA. Residual phytotoxicity effects of paraquat, glyphosate and glufosinate ammonium herbicides in soils from field- treated plots. *International Journal of Agriculture and Biology*; 2009;11:214-216.

38. Baboo M, Pasayat M, Samal A, Kujur M, Maharana JK, Pate AK. Effect of four herbicides on soil organic carbon, microbial biomass- C, enzyme activity and microbial populations in agricultural soil. *International Journal of Research in Environmental Science and Technology*. 2013;3(4):100-112.
39. Lone AH, Raverkar KP, Pareek N. In-vitro effects of herbicides on soil microbial communities. *The Bioscan*. 2014;9(1):11-16.
40. Ataikiru TL, Okorhi-Damisa FB. Biodegradation of carbofuran and paraquat by indigenous soil microorganisms. *Journal of Advances in Biology & Biotechnology*. 2022;25(10):24-34.
41. Alharbi SA, Arunachalam C, Murugan AM, Wainwright M. Antibacterial activity of actinomycetes isolated from terrestrial soil of Saudi Arabia. *Journal of Food, Agriculture and Environment*. 2012; 10(2): 1093-1097.
42. Organization for Economic Co-operation and Development (OECD). Environment, health and safety publication series on pesticides persistent, bioaccumulative and toxic pesticides in OECD member countries result of survey on data requirements and risk assessment approaches. 2003;15:1-67.
43. Lima MP, Cardoso DN, Soares AM, Loureiro S. Carbaryl toxicity prediction to soil organisms under high and low-temperature regimes. *Ecotoxicol Environ Saf*. 2015;114:263–27.
44. Arimoro F. Heavy metal content in the African giant snail *Achachatina marginata* in Southern Nigeria. *Folia Malacologica*. 2008;16(1):31-34.
45. Diez MC, Elgueta S, Rubilar O, Tortella GR, Schalchli H, Bornhardt C, et al. Pesticide dissipation and microbial community changes in a biopurination system: influence of the rhizosphere. *Biodegradation*. 2017;28:395-412.
46. Tudararo-Aherobo LE, Ataikiru TL. Effects of chronic use of herbicides on soil physicochemical and microbiological characteristics. *Microbiology Research Journal International*. 2020;30(5):9-19.
47. Ławniczak Ł, Woźniak-Karczewska M, Loibner AP, Heipieper HJ, Chrzanowski L. Microbial degradation of hydrocarbons: Basic principles for bioremediation: A review. *Molecules*. 2020;25(4):856.
48. Boto ML, Magalthes C, Perdigao R. Harnessing the potential of Native Microbial Communities for Bioremediation of oil spills in the Iberian Peninsula NW Coast. *Frontiers in Microbiology*. 2021;12: 1633-1659.
49. Jones AM, James II, Akpan PS, Eka II, Oruk AE, Ibuot AA. Characterization of Hydrocarbon Utilizing Bacteria in waste engine oil impacted sites; 2021.
50. Tudararo-Aherobo LE, Okorhi- Damisa FB. Effects of biostimulation and bioaugmentation on microbial growth and bioremediation of hydrocarbon contaminated soils. *International Journal of Scientific Development and Research*. 2023b;8(3):
51. Okorhi-Damisa FB, Tudararo-Aherobo LE. Monitoring the degradation of total petroleum hydrocarbon in hydrocarbon impacted site using a consortium of hydrocarbon utilizing bacteria. *Journal of Advances in Microbiology Research*. 2023;4(1):123-127.
52. Vandana LJ, Rao PC, Padmaja G. Effect of herbicides and nutrient management on soil enzyme activity. *Journal of Rice Resources*. 2012;5:1-12.
53. De-Silver SFC, Gomed de Almeida NMP, da Rocha e Silva S. Soil remediation: An overview of technologies and trends. *Energies*. 2020;13(18):4664.
54. Khalid S, Baloo L, Kumar SN. Bioremediation of Total Petroleum Hydrocarbons (TPH) by Bioaugmentation and Biostimulation in Water with Floating Oil Spill Containment Booms as Bioreactor Basin. *International Journal of Environmental Research and Public Health*; 2021.
55. Kopittke PM, Enzo L. Soil and the intensification of agriculture for global security, *Science Direct on Environment International*. 2019;132(5):1050-1078.
56. Zain MMM, Mohamad RB, Sijam K, Morshed MM, Awang Y. Effects of selected herbicides on soil microbial populations in oil palm plantation of Malaysia: A microcosm experiment. *African Journal of Microbiology and Resources*. 2013;7(5): 367-374.
57. Fenner K, Canonica S, Wackett LP, Eisner M. Evaluating pesticide degradation in the environment: blind spots and emerging opportunities. *Science*. 2013;341(6147): 752–758.

58. Vischetti C, Casucci C, De Erardi A, Monaci E, Tiano L, Marcheggiani F, Ciani M, Comitina F, Marini E, Taskin E, Puglisi E. Sub-lethal effects of pesticides on the DNA of soil organisms as early ecotoxicological biomarkers. *Frontiers in Microbiology*. 2020;11:1892.
59. Karpouzas DG, Vryzas Z, Marti-Lauret F. Pesticide soil microbial toxicity: setting the
- sce for a new pesticide risk assessment for soil microorganisms (IUPAC Technical Report). *Pure and Applied Chemistry*. 2022;94(10):1161-1194.
60. Jiang YM, Lin D, Guan XJ, Wang JF, Cao GP, Zhu D et al. Effects of herbicide used with years (8+1) on soil enzymic activity and microbial population diversity. *J. Soils Sediments*. 2017;17:2490-2499.

© Copyright (2024): Author(s). The licensee is the journal publisher. This is an Open Access article distributed under the terms of the Creative Commons Attribution License (<http://creativecommons.org/licenses/by/4.0>), which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

*Peer-review history:*

*The peer review history for this paper can be accessed here:*

<https://prh.globalpresshub.com/review-history/1533>